Department of Licensing and Regulatory Affairs, Bureau of Fire Services, Storage Tank Division P.O. Box 30033, Lansing, MI 48909

NOTICE OF PROPOSED INSTALLATION OF UNDERGROUND STORAGE TANKS **Pre-Registration for Underground Storage Tanks**

This information is required under Part 211, Underground Storage Tank Regulations, of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended, being Sections 324.21101 through 324.21113 of the Michigan Compiled Laws Annotated. A person who violates Part 211 or a rule promulgated under Part 211, or who knowingly submits false information shall be subject to a misdemeanor and/or civil penalties not to exceed \$5,000 per violation.

This form must be completed and submitted to the Bureau of Fire Services a minimum of 45 days PRIOR to installation of the underground storage tank system. Complete the required information in accordance with the Michigan Underground Storage Tank Rules, R 29.2101 et seq. and the Storage and Handling of Flammable and Combustible Liquids Rules, R 29.5601 et seq. Parts 2 and 3 for underground installations as cited below. The manufacturer and part number must be indicated next to the appropriate item. The item numbers correspond to the Typical Underground Storage Tank Installation diagram on page 3. This form is not intended to list all of the requirements that may be applicable. Mail the completed form to the address at the bottom of page 2. THE UST SYSTEM SHALL NOT BE BROUGHT INTO USE UNTIL FORM BFS-3821, REGISTRATION FOR UNDERGROUND STORAGE TANKS, IS COMPLETED AND SUBMITTED TO THE CASHIERS OFFICE, DEPARTMENT OF LICENSING AND REGULATORY AFFAIRS WITH THE \$100.00 PER TANK REGISTRATION FEE.

Please direct any questions to the Bureau of Fire Services, Storage Tank Division, at 517-335-7211.

FACILITY NAME		NEW ASSIGNED TANK NUMBER(S)			FACILITY ID NUMBER	
FACILITY STREET ADDRESS (PO BOX NOT ACCEPTABLE)			CONTACT PERSON (AT LOCATION)			AREA CODE & TELEPHONE NUMBER
CITY			COUNTY		STATE MI	ZIP CODE
SUBMITTER'S NAME			STREET ADDRESS			AREA CODE & TELEPHONE NUMBER ()
CITY			STATE	_		ZIP CODE
Item No.	DESCRIPTION	MANUFACTURER & PA	ART NO.	NO.	DESCRIPTION	MANUFACTURER & PART NO.
1.	TANK DESIGN AND CONSTRUCTION: Section 280.20(a), 280.20(d), 280.32 & Section 22.4.2 of FL/CL Part 2. Concrete; Steel - UL58; Fiberglass – UL 1316. Corrosion protection - ACT 100. Dimension, Capacity &			5.	ANCHORING OF TANK: Section 23.14 of FL/CL Part 2. In areas subject to flooding or high water table. NOTE: Tie-down straps.	
	Contents.					
2.	BURIAL DEPTH COVER: Section 23.5.2.1 of FL/CL Part 2. Minimum 2-foot or 1-foot earth & 4-inch reinforced concrete with no vehicular traffic. Minimum 3-foot or 18-inch earth & 6-inch concrete or 8-inch asphalt with vehicular traffic.			6.	CORROSION PROTECTION FOR TANK: Section 280.20(a) & Section 23.3.5 of FL/CL Part 2. Fiberglass tanks, steel tanks with cathodic protection, composite steel tanks, are acceptable.	
3.	BACKFILL MATERIAL SURROUNDING TANK: Section 23.5.1 of FL/CL Part 2. Per tank manufacturer.			7.	MONITORING OF CATHODIC PROTECTION: Section 280.31. Test station-wires to ground surface for access.	
4.	TANK LOCATION: Section 280.20(d) & Section 23.4 of FL/CL Part 2. 10' from building. 3' for class I or 1' for class II to pit or property line; also to avoid loads transmitted by building foundation- tank outside 45 degree angle. Include site map. (#21)			8.	PIPING MATERIAL: Section 280.20(b), 280.20(d), 280.32 & Section 27.6.5 of FL/CL Part 2. Double-walled steel, fiberglass, or other approved material. Metallic piping shall be cathodically protected and dielectrically isolated.	

NOTICE OF PROPOSED INSTALLATION OF UNDERGROUND STORAGE TANKS (continued) Pre-Registration for Underground Storage Tanks

			3		
Item No.	DESCRIPTION	MANUFACTURER & PART NO.	NO.	DESCRIPTION	MANUFACTURER & PART NO.
9.	CORROSION PROTECTION FOR PIPING: Section 280.20(b). Metallic piping (including flexible connectors) requires cathodic protection; and dielectric couplings at tank and dispenser to isolate the piping.		15.	OVERFILL PROTECTION: Section 280.20(c) (1) (ii). Audible alarm or flow restricted when tank is 90% full, or an automatic shutoff of flow into the tank when the tank is 95% full.	
10.	RELEASE DETECTION FOR TANK & PIPING: Section 280.40(a), Section 280.41 & Section 280.42. Must be able to detect a release from any portion of the tank and piping.	a) _{TANK:} b) _{PIPING:}	16.	SPILL PROTECTION AROUND FILL PIPE: Section 280.20(c). Equipment to prevent release of product to the environment when the transfer hose is detached from the fill pipe. Sealed to prevent entry of product into the ground.	
11.	VENT PIPING: Section 27.8.2 of FL/CL Part 2. Steel above ground; outlet above snow level, minimum 12 feet above grade for class I.		17.	AREA BENEATH & AROUND DISPENSER: Section 28.9 of FL/CL Part 2. Prevent leaks and spills from reaching groundwater, surface water, and subsurface soils.	
12.	EMERGENCY SHEAR/FIRE VALVE: Section 6.3.9 and 6.3.10 of FL/CL Part 3. Required on submerged pumping systems, rigidly anchored. Suction systems require check valve or pressure regulating valve under the dispenser.		18.	PROTECTION AGAINST COLLISION: Section 6.3.4 of FL/CL Part 3. Raised concrete island or crash posts. NOTE: Local ordinances may be more stringent.	
13.	EMERGENCY BREAKAWAY DEVICE: Section 6.5.2 of FL/CL Part 3. Installed on each hose that dispenses a liquid. Designed to retain liquid on both sides of the breakaway point.		19.	DISPENSING DEVICE and NOZZLE: Section 6.6 of FL/CL Part 3. Must be listed and identified as to product it dispenses. Self-service needs special feature of nozzle that prevents resumption of flow once pump is stopped	
14.	LOCATION OF DISPENSER: Section 6.2.1, 6.3.4, 6.3.5 & 9-4 of FL/CL Part 3. 10 feet from property lines, combustible building walls, and building openings. In clear view of attendant. Within 100 feet of emergency shutoff switch for self-serve.		20.	SAFETY: Section 6.7 of FL/CL Part 3. Dispensing devices shall have one or more identified emergency shutoff devices. Section 9.2.5.2 Each motor fuel dispensing facility shall be provided with fire extinguishers per NFPA 10.	


21. A plot plan showing structures, roads, railroads, property lines, and easements within 25 feet of the UST system. Section 280.22 - attach to this form.

22. The location of all applicable drinking water wells and surface water intakes within 2000 feet of the UST system. Section 280.22 - attach to this form.

23. A diagram of the UST system. Section 280.22 - attach to this form.

20: A diagram of the Cot Cyclom: Cotton 200:22 diagon to the form:						
MAIL TO:	OVERNIGHT MAIL:					
Department of Licensing and Regulatory Affairs	Department of Licensing and Regulatory Affairs	Page 2 of 3				
Bureau of Fire Services, Storage Tank Division	Bureau of Fire Services, Storage Tank Division	DEC 0000/D 40/44				
P.O. Box 30033, Lansing, MI 48909	3101 Technology Boulevard, Suite H, Lansing, MI 48910	BFS-3820(Rev 10/14)				

TYPICAL UNDERGROUND STORAGE TANK INSTALLATION



Page 3 of 3 BFS-3820 (Rev 10/14)